Name: Jefferson Langbid	Date Performed:
Course/Section: CPE 232-CPE31S23	Date Submitted:
Instructor: Dr. Taylar	Semester and SY:
Activity 15: OpenStack Installation (Neutron, Horizon, Cinder)	

1. Objectives

Create a workflow to install OpenStack using Ansible as your Infrastructure as Code (IaC).

2. Intended Learning Outcomes

- 1. Analyze the advantages and disadvantages of cloud services
- 2. Evaluate different Cloud deployment and service models
- 3. Create a workflow to install and configure OpenStack base services using Ansible as documentation and execution.


3. Resources

Oracle VirtualBox (Hypervisor)

1x Ubuntu VM or Centos VM

4. Tasks

- 1. Create a new repository for this activity.
- 2. Create a playbook that converts the steps in the following items in https://docs.openstack.org/install-guide/
 - a. Neutron
 - b. Horizon
 - c. Cinder
 - d. Create different plays in installing per server type (controller, compute etc.) and identify it as a group in the Inventory file.
 - e. Add, commit and push it to your GitHub repo.
- **5.** Output (screenshots and explanations)



I created a new github repository for the activity

```
jefferson@LocalMachine: ~/HOA15_NHC/NHC

GNU nano 6.2 inventory

[remote_users]
192.168.56.104

[controller]
192.168.56.104
```

```
GNU nano 6.2

[defaults]

inventory = inventory
host_key_checking = False

deprecation_warnings = False

ansible_user = jefferson
private_key_file = ~/.ssh/
```


I created the ansible.cfg and inventory for the ansible.

```
jefferson@LocalMachine: ~/HOA15_NHC/NHC
  Ŧ
  GNU nano 6.2
                                        NHC.YML *
 - hosts: all
   become: true
   pre_tasks:
   - name: Install updates for ubuntu
     apt:
       upgrade: dist
       update_cache: yes
     changed_when: false
     when: ansible_distribution == "ubuntu"
Create the yml for the ansible
 jefferson@LocalMachine:~/HOA15_NHC/NHC/roles$ tree
         └─ main.yml
         └─ main.yml
         └─ main.yml
6 directories, 3 files
```

I created the roles for the installation of OpenStack

```
GNU nano 6.2
                                    main.yml *
name: Install Cinder for ubuntu
apt:
 name:
   - cinder-api
   - cinder-backup
  state: present
  update_cache: yes
name: Configure the Cinder
  dest: /etc/cinder/cinder.conf
  content:
    [DEFAULT]
    auth_strategy = keystone
    [keystone_authtoken]
    www_authenticate_uri = http://controller:5000
    auth_url = http://controller:5000
    memcached_servers = controller:11211
    auth_type = password
    project_domain_name = default
    user_domain_name = default
    project_name = service
    username = cinder
    password = 1234
```


Main.yml of Cinder



```
jefferson@LocalMachine: ~/HOA15_NHC/NHC/roles/Neutro...
                                                 Q = (-)
 GNU nano 6.2
                                main.yml *
 name: Install Neutron for ubuntu
  apt:
   name: neutron-linuxbridge-agent
   state: present
   update cache: yes
- name: Configuring the Neutron
 copy:
   dest: /etc/neutron/neutron.conf
   content:
     [DEFAULT]
     auth_strategy = keystone
     [keystone authtoken]
     www_authenticate_uri = http://controller:5000
     auth_url = http://controller:5000
     memcached_servers = controller:11211
     auth_type = password
     project_domain_name = default
     user_domain_name = default
     project_name = service
     username = neutron
     password = 1234
- name: Restarting Neutron
                       main.yml of Neutron.
TASK [Horizon : Install Horizon for ubuntu] ****************
changed: [192.168.56.104]
TASK [Horizon : Configure the Horizon] ****************************
changed: [192.168.56.104]
ok: [192.168.56.104]
changed: [192.168.56.104]
```

The code ran successfully and installed the Neutron, Cinder, and Horizon.

```
jefferson@Server2:~$ sudo systemctl status neutron-linuxbridge-agent
neutron-linuxbridge-agent.service - Openstack Neutron Linux Bridge Agent
     Loaded: loaded (/lib/systemd/system/neutron-linuxbridge-agent.service; en>
     Active: active (running) since Sat 2022-12-10 17:37:45 PST; 4s ago
   Process: 10084 ExecStartPre=/bin/mkdir -p /var/lock/neutron /var/log/neutr
   Process: 10085 ExecStartPre=/bin/chown neutron:neutron /var/lock/neutron /
   Process: 10086 ExecStartPre=/sbin/modprobe br netfilter (code=exited, stat>
  Main PID: 10087 (neutron-linuxbr)
     Tasks: 1 (limit: 1075)
     Memory: 102.2M
        CPU: 1.547s
     CGroup: /system.slice/neutron-linuxbridge-agent.service
              —10087 /usr/bin/python3 /usr/bin/neutron-linuxbridge-agent --con>
Dec 10 17:37:45 Server2 systemd[1]: neutron-linuxbridge-agent.service: Schedul>
Dec 10 17:37:45 Server2 systemd[1]: Stopped Openstack Neutron Linux Bridge Age
Dec 10 17:37:45 Server2 systemd[1]: neutron-linuxbridge-agent.service: Consume>
jefferson@Server2:~$ sudo systemctl status cinder-backup
cinder-backup.service - OpenStack Cinder Backup
     Loaded: loaded (/lib/systemd/system/cinder-backup.service; enabled; vendo
     Active: active (running) since Sat 2022-12-10 17:38:29 PST; 125ms ago
       Docs: man:cinder-backup(1)
   Main PID: 10277 (cinder-backup)
      Tasks: 2 (limit: 1075)
     Memory: 300.0K
        CPU: 17ms
     CGroup: /system.slice/cinder-backup.service
               -10277 /bin/sh /etc/init.d/cinder-backup systemd-start
              -10279 whoami
Dec 10 17:38:29 Server2 systemd[1]: cinder-backup.service: Scheduled restart j
Dec 10 17:38:29 Server2 systemd[1]: Stopped OpenStack Cinder Backup.
Dec 10 17:38:29 Server2 systemd[1]: cinder-backup.service: Consumed 1.679s CPU
Dec 10 17:38:29 Server2 systemd[1]: Started OpenStack Cinder Backup.
lines 1-16/16 (END)
```



```
ſŦ
                    jefferson@LocalMachine: ~/HOA15_NHC/NHC
no changes added to commit (use "git add" and/or "git commit -a")
jefferson@LocalMachine:~/HOA15_NHC/NHC$ git add NHC.YML
jefferson@LocalMachine:~/HOA15_NHC/NHC$ git add inventory
jefferson@LocalMachine:~/HOA15_NHC/NHC$ git add roles/Cinder/tasks/main.yml
jefferson@LocalMachine:~/HOA15_NHC/NHC$ git add riles/Horizon/tasks/main.yml
warning: could not open directory 'NHC/riles/Horizon/tasks/': No such file or d
irectory
fatal: pathspec 'riles/Horizon/tasks/main.yml' did not match any files
jefferson@LocalMachine:~/HOA15_NHC/NHC$ git add roles/Horizon/tasks/main.yml
jefferson@LocalMachine:~/HOA15_NHC/NHC$ git add roles/Neutron/tasks/main.yml
jefferson@LocalMachine:~/HOA15_NHC/NHC$ git commit -m "HOA15"
[main fca224c] HOA15
5 files changed, 26 insertions(+), 49 deletions(-)
rewrite NHC/roles/Horizon/tasks/main.yml (81%)
jefferson@LocalMachine:~/HOA15_NHC/NHC$ git push origin main
Enumerating objects: 27, done.
Counting objects: 100% (27/27), done.
Compressing objects: 100% (9/9), done.
Writing objects: 100% (15/15), 1.32 KiB | 675.00 KiB/s, done.
Total 15 (delta 3), reused 0 (delta 0), pack-reused 0
remote: Resolving deltas: 100% (3/3), completed with 2 local objects.
To github.com:jlangbid13/HOA15_NHC.git
   867ea1a..fca224c main -> main
jefferson@LocalMachine:~/HOA15_NHC/NHC$
```

I added, committed, and pushed it to my github repository.

jlangbid13/HOA15 NHC (github.com)

Reflections:

Answer the following:

1. Describe Neutron, Horizon and Cinder services

Neutron- A network service responsible for creating network connectivity and network services. It is capable of connecting with vendor network hardware through plug-ins.

Horizon- A dashboard that creates a GUI for users to control the OpenStack cloud. This is an extensible framework to which vendors can add features. Horizon uses the same APIs that are exposed to users.

Cinder- A block storage service responsible for creating and managing external storage. It is capable of connecting to vendor storage hardware through plug-ins.

Conclusions:

All in all, in this activity, we are tasked to install the prerequisites of openstack which is Neutron, Horizon, and Cinder using ansible to another server. First, I created a github repository and cloned it to the local machine and also created the ansible.cfg and then the inventory for the ansible. After that I created the roles for the computer and controller. I created the yml for the installation of the prerequisites which are Neutron, Horizon, and Cinder. I created the role directory to store the main.yml of each role and after inputting the codes the ansible ran successfully. I added, committed, and pushed the files to my github repository